

# **An assessment of risk factors impacting cost variability in Nigerian construction projects**

Babatunde Dosumu<sup>1</sup>, Obuks Ejohwomu<sup>1</sup>, Akilu Yunusa-Kaltungo<sup>1</sup> and Olufemi Daramola<sup>2</sup>

<sup>1</sup>Department of Mechanical, Aerospace and Civil Engineering, University of Manchester, Oxford Rd, Manchester; babatunde.dosumu@manchester.ac.uk

<sup>2</sup>Department of Quantity Surveying, The polytechnic Ibadan, Oyo state Nigeria

## **Abstract:**

According to a review of different authors' work, there are numerous risk factors that could impact the final account sums (FAS) of construction projects, causing variations in contract sum (CS). By minimising the variability between the final account sum FAS and CS, a compelling risk study could help resolve this issue. This research is concerned with the variance amidst CS and FAS while assuming that the observed variance is due to risk. The research adopted a convenience sampling technique, non-probability, purposive and definitive. Data was collected through a questionnaire survey from 43 stakeholders that showed interest from the identified 55 experts in the Nigerian construction sector during a conference organised by the Quantity surveyor's registration board of Nigeria (QSRBN). A quantitative investigation identified the critical risk factors that influence the precision of CS. The findings indicated fifteen significant risk causing variance between FAS and CS (cost variability). These check disparities in construction project planned costs during construction and the observed risk factors considered the concern of project advisors. In addition, the study offers practical solutions that suggest creating an effective mitigation plan for the construction sector by using a framework that supports risk management in project delivery. As a result, five highly significant risk variables in traditionally procured construction projects that initiate variance amidst CS and FAS: Poor programme scheduling, other risks, Availability of design information, Fluctuation and Type of client, which will be considered to develop a construction project risk management framework that will encourage sustainability of the Nigerian construction industry.

## **Keywords:**

Construction, project risk, cost variability, contract sum, final account sum, Nigeria.

## **1 Introduction**

Nigeria's construction industry is significant for employment and economic growth. Furthermore, the National Bureau of Statistics (2021) asserts that Nigeria's construction industry provided about 3.21% of the gross domestic product (GDP) in 2021. In Nigeria, the construction industry is one of the significant industries that contribute appreciably to the nation's development (Wibowo, 2004; Khan et al., 2011). This contribution classifies the sector as a critical driver of economic development, having occupied the eighth position in the sectoral contribution to the real Nigeria GDP. Amongst unique attributes that distinguish the

construction industry from all other industries include physical nature, organisation of the construction process, and one-off project designs, among others. (Ashworth and Hogg 2007). However, the industry is known as one sector that is vulnerable to risk. Most risk management studies have collected data on risk management from East Asia, Europe, the Middle East, and the United States (El-Sayegh and Mansour 2015). Furthermore, the cost is one of the factors used in measuring construction project success (Ameyaw *et al.*, 2015). It is thus noteworthy that accurate estimation of contract sum continues to pose challenges to project stakeholders.

The primary concern is how risk factors cause variability between the contract sum (CS) and the final account sum (FAS). This study pursues to develop a framework that will influence, support, and promote effective risk management practices in the Nigerian construction industry. There is an observed differences in budgeted costs amidst the CS and FAS in New Zealand (NZ), ranging between - 14% and +16%. (Adafin *et al.*2015). Adafin (2017), in a follow-up study researched in New Zealand with cost data from completed building projects, observed that the variance between CS and FAS differs significantly. These findings implied that cost variability occurs in the construction industries in developed countries. Cost variability could be due to design and construction risks (Xia *et al.*, 2017). The observed variance between CS and FAS could be reduced if risk items were identified and priced while estimating the contract sum. In addition, cost variability could vary with procurement, project complexity and project types (Adafin *et al.*, 2016).

Primarily, the objective is how these risk factors inherent in construction projects interact to cause variability between CS and FAS. Unfortunately, limited attention has been given to this area in Nigeria. While clients are becoming uncomfortable with seeing their projects completed over budget, this study attempts to assess risk factors impacting the cost of construction projects in Nigeria. The research outcome will be backed up by developing a practical risk management framework for more accurate cost estimation in the construction industry in Nigeria.

## **2 Literature Review**

The absence of a cost estimation framework causes cost variability in construction, affecting efficiency and effectiveness from the planning stage through the project's final account stage (Zakaria *et al.*, 2013). Doloi (2011) observed that proper cost estimation is a significant impediment for project stakeholders. Researchers such as Zakaria *et al.* (2013), Doloi (2011), Ameyaw *et al.* (2015), Salahi and Ali (2018), and others have acknowledged that cost variability exists in the construction industry and that it is a significant problem in the industry's growth.

Several studies (Enshassi *et al.*, 2013; Adafin *et al.*, 2018: Adafin *et al.*, 2016, Adafin, 2017 Agyekum-Mensah, 2018) have identified risks that affect construction project budgetary performance. Various causes, evidence, and arguments in construction management research (Adafin *et al.*, 2020: Adafin *et al.*, 2018: Adafin, 2017; Agyekum-Mensah, 2018; Love and Ahiaga-Dagbui 2018; Yap *et al.*, 2018) suggested that it is uncommon to discover a project where the CS matches the FAS. As a result, an effective risk mitigation plan (a deterministic system to risk) for construction projects should reduce budget/cost and schedule/time variability (Hwang *et al.*, 2014). Dosumu *et al.*, (2021), identified between 1-40 risk causing

cost variability in Nigeria, which includes Clients change/Changes in owner's requirements, Client's brief, Type of client, Defective design, and specification, among others. As a partial solution, this study proposes using risk analysis to reduce the variances between CS and FAS of construction projects. Regrettably, there is a dearth of literature and research on construction project risk in Nigeria, Dosumu et al., (2021), identified 79 authors and only 6 authors from Africa that researched on cost variability, and only 3, (4.48%) authors from Nigeria which Identifies and measures risk variables of Nigerian construction projects, and how these interact to explain the vast range between CS and FAS. As a result, this study investigates what causes variability between CS and FAS in construction projects from the standpoint of construction stakeholders (consultants, clients, contractors, and regulatory authorities) and how to evaluate the causes of such discrepancies as observed.

### 3 Methodology

The methodology followed Fellows and Liu (2015), and a questionnaire containing closed-ended questions was sent to participants drawn from the databases of participants who actively participated in a conference organised by the Quantity surveyor's registration board of Nigeria (QSRBN) in May/June 2021. Based on a review of the literature, 29 relevant risk factors were observed. To analyse the top significant risks from the observed 29 indicators, analysis and ranking were done using a cut-off point of 3.0 and above, according to Adafin et al. (2016). Rating by respondents using a five-point Likert as used by Arif et al. (2015) and Odeyinka et al. (2012) was adopted. As a result, an interval scale, allowing the data to be used in various statistical analyses, was used. Following Naoum (2007), on sampling, the sampling frame was drawn from the databases of participants who actively participated in a conference organised by the Quantity surveyor's registration board of Nigeria in May/June 2021. Only 43 of the 55 complete replies obtained were involved in traditionally procured construction projects (see Table 1), a 78 per cent response rate higher than Simpeh et al. (2015) proposed response rate of 19. 5 per cent for relevant data. The mean score analysis, degree of risk and analysis of variance (Anova) from the stakeholders were also used to analyse the responses as used by (Adafin et al. 2016), (Allahaim, and Liu, 2015), (Odeyinka et al., 2012) and (Offei-Nyako et al., 2016).

The responses were sorted to evaluate the extent, impact, and degree of risk, as adopted by Adafin et al. (2016), (2017) and (2020). The degree-of-risk values were determined using mean scores (MS), of risk impact and extent of risk. The "Degree of Risk" metric as shown in Table 3 was used to rank the discovered risk variables.  $R = P \times I$  (Offei-Nyako et al., 2016).  $R$  denotes the degree of risk,  $P$  denotes the extent of risk occurrence, and  $I$  denotes the perceived impact on a project. Furthermore, the study measured the degree of agreement among participants' rankings in evaluating risk variables using Analysis of variance (Anova)

Analysis of the extent of a risk happening, its perceived impacts and the 'degree-of-risk' scores in traditionally procured projects are summarised in Tables 3,4and 5 (Risk factors' means and rankings). The combined sample's 'degree-of-risk' scores range from 3.73 to 15.08. A few risk variables are in the range of 7.58 to 15.08, demonstrating the complex interaction of the most critical risk factors. The top-five risk factors that could influence cost variability include poor programme scheduling, other risks, availability of design information, fluctuation, and type of client, according to the consequent ranking of the 29 risk factors. In addition to the mean

ranking analysis, the study used a 't-test' analysis to determine the stakeholders' concordance, from which opinions were sought.

## 4 Data Analysis and Results

Table 1 provides a detailed assessment of the respondents and their firms, study locations, educational and professional qualification and experience in cost and risk management, and the projects they manage to attest that the qualifications and experience required for the purpose are available.

**Table 1:** Participants' demographic information

|                                                 |                          | Frequency | Percent | Valid Percent | Cumulative Percent |
|-------------------------------------------------|--------------------------|-----------|---------|---------------|--------------------|
| Project Location                                | Lagos                    | 21        | 48.8    | 48.8          | 48.8               |
|                                                 | Abuja                    | 22        | 51.2    | 51.2          | 100                |
|                                                 | Total                    | 43        | 100     | 100           |                    |
| Nature of Outfit                                | Consulting               | 23        | 53.5    | 53.5          | 53.5               |
|                                                 | Contracting              | 8         | 18.6    | 18.6          | 72.1               |
|                                                 | Client                   | 6         | 14      | 14            | 86                 |
|                                                 | Others                   | 6         | 14      | 14            | 100                |
|                                                 | Total                    | 43        | 100     | 100           |                    |
| Designation of Respondents                      | Architect                | 10        | 23.3    | 23.3          | 23.3               |
|                                                 | Quantity Surveyor        | 11        | 25.6    | 25.6          | 48.8               |
|                                                 | Contractor               | 8         | 18.6    | 18.6          | 67.4               |
|                                                 | Builder                  | 11        | 25.6    | 25.6          | 93                 |
|                                                 | Project Manager          | 3         | 7       | 7             | 100                |
|                                                 | Total                    | 43        | 100     | 100           |                    |
| Highest Educational Qualification               | Ph.D.                    | 5         | 11.6    | 11.6          | 11.6               |
|                                                 | Masters' degree          | 12        | 27.9    | 27.9          | 39.5               |
|                                                 | Bachelor's degree        | 13        | 30.2    | 30.2          | 69.8               |
|                                                 | Post-graduate            | 4         | 9.3     | 9.3           | 79.1               |
|                                                 | Diploma/Graduate diploma | 9         | 20.9    | 20.9          | 100.0              |
|                                                 | Total                    | 43        | 100.0   | 100.0         |                    |
| Highest Professional Qualification              | MNIA                     | 6         | 14.0    | 14.0          | 14.0               |
|                                                 | MNIQS                    | 11        | 25.6    | 25.6          | 39.5               |
|                                                 | MNIOB                    | 7         | 16.3    | 16.3          | 55.8               |
|                                                 | PMP                      | 3         | 7.0     | 7.0           | 62.8               |
|                                                 | FNIA                     | 4         | 9.3     | 9.3           | 72.1               |
|                                                 | FNIQS                    | 8         | 18.6    | 18.6          | 90.7               |
|                                                 | FNIOB                    | 4         | 9.3     | 9.3           | 100.0              |
|                                                 | Total                    | 43        | 100.0   | 100.0         |                    |
| Years of experience in Construction Works       | 1-10 years               | 5         | 11.6    | 11.6          | 11.6               |
|                                                 | 11-20 years              | 12        | 27.9    | 27.9          | 39.5               |
|                                                 | 21-30 years              | 19        | 44.2    | 44.2          | 83.7               |
|                                                 | 31-40 years              | 5         | 11.6    | 11.6          | 95.3               |
|                                                 | Over 40 years            | 2         | 4.7     | 4.7           | 100                |
|                                                 | Total                    | 43        | 100     | 100           |                    |
| Years of experience in Cost and Risk Management | 1-10 years               | 5         | 11.6    | 11.6          | 11.6               |
|                                                 | 11-20 years              | 12        | 27.9    | 27.9          | 39.5               |

|                                           |               | Frequency | Percent | Valid Percent | Cumulative Percent |
|-------------------------------------------|---------------|-----------|---------|---------------|--------------------|
|                                           | 21-30 years   | 19        | 44.2    | 44.2          | 83.7               |
|                                           | 31-40 years   | 5         | 11.6    | 11.6          | 95.3               |
|                                           | Over 40 years | 2         | 4.7     | 4.7           | 100                |
|                                           | Total         | 43        | 100     | 100           |                    |
| How long has your firm been in operation? | 1-10 years    | 5         | 11.6    | 11.6          | 11.6               |
|                                           | 11-20 years   | 12        | 27.9    | 27.9          | 39.5               |
|                                           | 21-30 years   | 19        | 44.2    | 44.2          | 83.7               |
|                                           | 31-40 years   | 5         | 11.6    | 11.6          | 95.3               |
|                                           | Over 40 years | 2         | 4.7     | 4.7           | 100.0              |
|                                           | Total         | 43        | 100.0   | 100.0         |                    |

Source: Data Analysis Result 2022

The focus was on building projects only with the traditional procurement system adopted for all, as seen in Table 2. The projects were executed between 2015 and 2020, with the highest number of these projects constructed in 2017 (23.3%). In the first three years (2015-2017), the frequency of the projects increased with each year but started dropping in the last three years, from the year (2018-to 2020). The reason may not be farfetched, with the possibility of the country's economic situation that affected all areas, including construction projects and their associated activities. The table also reveals the client type, which included government, with over half of the projects were awarded by the government (69.8%) while others were from private individuals (11.6%) or public (18.6%).

**Table 2:** Project specific information

|                            |             | Frequency | Percent | Valid Percent | Cumulative Percent |
|----------------------------|-------------|-----------|---------|---------------|--------------------|
| Project Type               | Building    | 43        | 100.0   | 100.0         | 100.0              |
| Procurement System Adopted | Traditional | 43        | 100.0   | 100.0         | 100.0              |
| Year of Project            | 2015        | 8         | 18.6    | 18.6          | 18.6               |
|                            | 2016        | 9         | 20.9    | 20.9          | 39.5               |
|                            | 2017        | 10        | 23.3    | 23.3          | 62.8               |
|                            | 2018        | 8         | 18.6    | 18.6          | 81.4               |
|                            | 2019        | 5         | 11.6    | 11.6          | 93                 |
|                            | 2020        | 3         | 7       | 7             | 100                |
|                            | Total       | 43        | 100     | 100           |                    |
| Client Type                | Private     | 5         | 11.6    | 11.6          | 11.6               |
|                            | Public      | 8         | 18.6    | 18.6          | 30.2               |
|                            | Government  | 30        | 69.8    | 69.8          | 100.0              |
|                            | Total       | 43        | 100.0   | 100.0         |                    |

Source: Data Analysis Result 2022

Considering other project characteristics such as project duration, contract sum, and final account sum, provided data were also grouped to assess and compare the data by group easily. It is essential to evaluate the stakeholder's perception of risk, correlation of coefficients, using mean value to deduce risk occurrence, risk impact and degree of risk as used by (Adafin et al. 2016), (Allahaim, and Liu, 2015), (Odeyinka et al., 2012) and (Offei-Nyako et al., 2016).and

Analysis of variance (Anova) was used to test of agreement/disagreement and the results shown in Table 3, 4 and 5.

Table 3 reveals breakdown of the degree of risk of the identified significant factors causing cost variability between contract sum and final account in construction projects and limited the risk factors to fifteen. With the top five risk factors being Poor programme scheduling, other risk, Availability of design information, Fluctuation and Type of client. Therefore, these identified significant risk factors should not be taken for granted as the consequence of their expression or occurrence can be detrimental if not discovered and curbed on time.

**Table 3:** Stakeholder's perception of degree of risk for identified significant risk factors causing cost variability

| Risk Factors                       | All   |      | Architect |      | Quantity Surveyor |      | Contractor |      | Builder |      | Project Manager |      |
|------------------------------------|-------|------|-----------|------|-------------------|------|------------|------|---------|------|-----------------|------|
|                                    | DoR   | Rank | DoR       | Rank | DoR               | Rank | DoR        | Rank | DoR     | Rank | DoR             | Rank |
| Poor programme scheduling          | 15.70 | 1    | 13.50     | 2    | 16.35             | 2    | 16.90      | 1    | 16.35   | 1    | 15.00           | 1    |
| Other risk (please state)          | 15.19 | 2    | 14.88     | 1    | 16.50             | 1    | 16.49      | 2    | 13.34   | 12   | 15.00           | 12   |
| Availability of design information | 14.33 | 3    | 12.47     | 8    | 14.73             | 7    | 15.75      | 4    | 14.95   | 2    | 12.99           | 2    |
| Fluctuation                        | 14.25 | 4    | 12.60     | 7    | 15.48             | 3    | 14.63      | 8    | 14.55   | 3    | 12.99           | 3    |
| Type of client                     | 14.13 | 5    | 13.05     | 5    | 15.48             | 3    | 14.49      | 11   | 13.75   | 6    | 12.99           | 6    |
| Delay in Resolving disputes        | 14.08 | 6    | 12.76     | 6    | 15.48             | 3    | 14.09      | 13   | 14.15   | 5    | 12.99           | 5    |
| Increase in finance rate           | 14.08 | 6    | 12.15     | 10   | 14.73             | 7    | 16.34      | 3    | 13.75   | 6    | 12.99           | 6    |
| Obtaining construction permits     | 14.02 | 8    | 13.34     | 3    | 14.65             | 10   | 15.65      | 5    | 13.08   | 14   | 12.99           | 14   |
| Under Estimation                   | 13.90 | 9    | 12.47     | 8    | 15.04             | 6    | 14.63      | 8    | 13.75   | 6    | 12.99           | 6    |
| Site condition                     | 13.87 | 10   | 11.70     | 15   | 14.42             | 11   | 15.21      | 6    | 14.47   | 4    | 12.99           | 4    |
| Act of God                         | 13.67 | 11   | 13.20     | 4    | 13.67             | 15   | 15.05      | 7    | 13.24   | 13   | 12.99           | 13   |
| Contractors default                | 13.51 | 12   | 12.15     | 10   | 13.96             | 12   | 14.63      | 8    | 13.47   | 11   | 12.99           | 11   |
| Shortage of materials              | 13.51 | 12   | 11.88     | 14   | 14.73             | 7    | 13.50      | 17   | 13.75   | 6    | 12.99           | 6    |
| Bureaucracy in Tendering method    | 13.41 | 14   | 12.15     | 10   | 13.96             | 12   | 13.89      | 16   | 13.75   | 6    | 12.99           | 6    |
| Accident during construction       | 11.79 | 15   | 10.80     | 15   | 12.16             | 15   | 13.14      | 15   | 10.90   | 15   | 12.99           | 15   |

Source: Data Analysis Result 2022

Table 4 revealed that both negative and positive correlations existed between the observed risk factors' occurrence and impact. The proposition from this result is that a positive correlation connotes a direct relationship while a negative correlation connotes an inverse or transposed relationship. The risk factor with the highest positive correlation was other risk, with a correlation coefficient of 0.382. This result implies a 38.2% correlation between the occurrence of this risk and its impact, which indicated that this risk factor, amongst others, had the highest measure between its occurrence and impact. This result denoted that an increase in the occurrence of this risk would cause a 38.2% increase in its impact; also, a

decrease in the occurrence of this risk would result in a 38.2% decrease in its impact. On the other hand, the risk factor with the most negligible positive correlation was Fluctuation in market demand with a correlation coefficient of 0.034; this means there was only a 3.4% correlation between the occurrence of this risk and its impact. It is also worth noting that this risk factor, amongst others, had the lowest positive correlation between its occurrence and impact. This result implied that an increase in the occurrence of this risk would cause a 3.4% increase in its impact; similarly, a decrease in the occurrence of this risk would result in a 3.4% decrease in its impact.

**Table 4:** Correlation results for risk occurrence and risk impact factors causing cost variability between contract sum and final account in construction projects

| Risk Factors                                    | Mean (RO) | Mean (RI) | CC        | Sig   | Remark |    | % C (A F) | ISR |
|-------------------------------------------------|-----------|-----------|-----------|-------|--------|----|-----------|-----|
| Other risk (please state)                       | 3.14      | 4.84      | .382*     | 0.012 | PWC    | S  | 38.2      | SR  |
| Accident during construction                    | 4.37      | 2.7       | -.370*    | 0.015 | NWC    | S  | 37.0      | SR  |
| Expertise of construction                       | 2.67      | 4.56      | 0.346*    | 0.023 | PWC    | S  | 34.6      |     |
| Over Estimation                                 | 2.72      | 4.53      | 0.302*    | 0.049 | PWC    | S  | 30.2      |     |
| Late arrival of materials                       | 2.72      | 4.53      | 0.3       | 0.05  | PWC    | NS | 30.0      |     |
| Changes in Clients taste                        | 2.56      | 4.6       | 0.287     | 0.062 | PWC    | NS | 28.7      |     |
| Method of construction                          | 2.65      | 4.56      | 0.284     | 0.065 | PWC    | NS | 28.4      |     |
| Availability and supply of materials and labour | 2.72      | 4.56      | 0.259     | 0.094 | PWC    | NS | 25.9      |     |
| Contractors' poor management                    | 2.67      | 4.47      | 0.243     | 0.116 | PWC    | NS | 24.3      |     |
| Obtaining construction permits                  | 3.14      | 4.47      | -0.237    | 0.126 | NWC    | NS | 23.7      | SR  |
| Site condition                                  | 3.14      | 4.42      | -0.231    | 0.137 | NWC    | NS | 23.1      | SR  |
| Bureaucracy in Tendering method                 | 3.02      | 4.44      | -0.23     | 0.139 | NWC    | NS | 23.0      | SR  |
| Insurance cost                                  | 2.72      | 4.47      | -0.23     | 0.139 | NWC    | NS | 23.0      |     |
| Government policy                               | 2.74      | 4.53      | 0.219     | 0.158 | PWC    | NS | 21.9      |     |
| Fluctuation                                     | 3.21      | 4.44      | -0.204    | 0.189 | NWC    | NS | 20.4      | SR  |
| Bad weather                                     | 2.7       | 4.49      | 0.186     | 0.233 | PWC    | NS | 18.6      |     |
| Use of inappropriate plant                      | 2.74      | 4.47      | 0.175     | 0.261 | PWC    | NS | 17.5      |     |
| Variations (Technical)                          | 2.63      | 4.6       | 0.173     | 0.267 | PWC    | NS | 17.3      |     |
| Type of client                                  | 3.16      | 4.47      | -0.171    | 0.274 | NWC    | NS | 17.1      | SR  |
| Act of God                                      | 3.09      | 4.42      | -0.153    | 0.327 | NWC    | NS | 15.3      | SR  |
| Mode of financing                               | 2.67      | 4.49      | 0.148     | 0.345 | PWC    | NS | 14.8      |     |
| Availability of design information              | 3.28      | 4.37      | -0.145    | 0.354 | NWC    | NS | 14.5      | SR  |
| Shortage of materials                           | 3.07      | 4.4       | -0.143    | 0.359 | NWC    | NS | 14.3      | SR  |
| Under Estimation                                | 3.16      | 4.4       | -0.142    | 0.365 | NWC    | NS | 14.2      | SR  |
| Delay in Resolving disputed                     | 3.19      | 4.42      | -0.123    | 0.432 | NWC    | NS | 12.3      | SR  |
| Contractor's default                            | 3.07      | 4.4       | -0.088    | 0.576 | NWC    | NS | 8.8       | SR  |
| Fluctuation in market demand                    | 2.79      | 4.49      | 0.034     | 0.827 | PWC    | NS | 3.4       |     |
| Increase in finance rate                        | 3.19      | 4.42      | -0.012    | 0.938 | NWC    | NS | 1.2       | SR  |
| Poor programme scheduling                       | 3.14      | 5         | No Result |       |        |    | 0.0       | SR  |

NWC - Negative Weak Correlation; PWC - Positive Weak Correlation; CC - Correlation Coefficient; %C - % of Correlation; S – Significant; NS - Not Significant; ISR - Identified Significant Risk (Source: Data Analysis Result 2022)

Table 5 revealed the result of ANOVA on the occurrence of risk factors causing cost variability between contract sum and final account in construction projects in Nigeria indicated that there was no significant difference in respondents' perceptions of the occurrence of all the identified risk factors associated with cost variability between contract sum and final account in construction projects in Nigeria based on their designations. Their f-value reveals this result at  $\text{sig} > 0.05$ . These risk factors include Accident during construction (f-value = 0.648 @  $p = 0.632$ ); Availability of design information (f-value = .780 @  $p = 0.545$ ); Fluctuation (f-value = 0.868 @  $p = 0.492$ ); Delay in Resolving disputed f-value = 0.701 @  $p = 0.596$ ); Other risk (f-value = 0.488 @  $p = 0.745$ ); and increase in finance rate (f-value = 1.473 @  $p = 0.230$ ) amongst others. The result implies that all the surveyed respondents perceived the occurrence of these risk factors the same way.

**Table 5:** Respondents' perception on occurrence of Risk Factors causing cost variability between contract sum and final account in construction projects

| Extent of Risk                              | All  |    | Architect |    | Quantity Surveyor |    | Contractor |    | Builder |    | Project Manager |   | f value | p value |
|---------------------------------------------|------|----|-----------|----|-------------------|----|------------|----|---------|----|-----------------|---|---------|---------|
|                                             | Mean | R  | Mean      | R  | Mean              | R  | Mean       | R  | Mean    | R  | Mean            | R |         |         |
| Accident during construction                | 4.37 | 1  | 4.50      | 1  | 4.18              | 1  | 4.38       | 1  | 4.45    | 1  | 4.33            | 1 | .648    | .632    |
| Availability of design information          | 3.28 | 2  | 2.90      | 4  | 3.45              | 5  | 3.50       | 3  | 3.36    | 2  | 3.00            | 2 | .780    | .545    |
| Fluctuation                                 | 3.21 | 3  | 2.80      | 9  | 3.55              | 2  | 3.25       | 8  | 3.27    | 3  | 3.00            | 2 | .868    | .492    |
| Delay in Resolving disputed                 | 3.19 | 4  | 2.90      | 4  | 3.55              | 2  | 3.13       | 12 | 3.18    | 5  | 3.00            | 2 | .701    | .596    |
| Increase in finance rate                    | 3.19 | 4  | 2.70      | 10 | 3.45              | 5  | 3.63       | 2  | 3.09    | 7  | 3.00            | 2 | 1.473   | .230    |
| Type of client                              | 3.16 | 6  | 2.90      | 4  | 3.55              | 2  | 3.13       | 12 | 3.09    | 7  | 3.00            | 2 | .741    | .570    |
| Under Estimation                            | 3.16 | 6  | 2.90      | 4  | 3.45              | 5  | 3.25       | 8  | 3.09    | 7  | 3.00            | 2 | .509    | .729    |
| Other risk (please state)                   | 3.14 | 8  | 3.10      | 2  | 3.36              | 10 | 3.38       | 4  | 2.82    | 15 | 3.00            | 2 | .488    | .745    |
| Obtaining construction permits              | 3.14 | 8  | 2.90      | 4  | 3.36              | 10 | 3.38       | 4  | 3.00    | 13 | 3.00            | 2 | .525    | .718    |
| Poor programme scheduling                   | 3.14 | 8  | 2.70      | 10 | 3.27              | 12 | 3.38       | 4  | 3.27    | 3  | 3.00            | 2 | .884    | .483    |
| Site condition                              | 3.14 | 8  | 2.60      | 16 | 3.45              | 5  | 3.38       | 4  | 3.18    | 5  | 3.00            | 2 | 1.112   | .365    |
| Act of God                                  | 3.09 | 12 | 3.00      | 3  | 3.27              | 12 | 3.25       | 8  | 2.91    | 14 | 3.00            | 2 | .285    | .886    |
| Shortage of materials                       | 3.07 | 13 | 2.70      | 10 | 3.45              | 5  | 3.00       | 17 | 3.09    | 7  | 3.00            | 2 | .914    | .466    |
| Contractor's default                        | 3.07 | 13 | 2.70      | 10 | 3.27              | 12 | 3.25       | 8  | 3.09    | 7  | 3.00            | 2 | .610    | .658    |
| Bureaucracy in Tendering method             | 3.02 | 15 | 2.70      | 10 | 3.27              | 12 | 3.00       | 17 | 3.09    | 7  | 3.00            | 2 | .433    | .784    |
| Fluctuation in market demand                | 2.79 | 16 | 2.60      | 16 | 3.00              | 16 | 3.13       | 12 | 2.45    | 18 | 3.00            | 2 | 1.345   | .271    |
| Government policy                           | 2.74 | 17 | 2.50      | 22 | 2.91              | 17 | 3.00       | 17 | 2.55    | 17 | 3.00            | 2 | .807    | .529    |
| Use of inappropriate plant                  | 2.74 | 17 | 2.40      | 26 | 2.82              | 20 | 3.13       | 12 | 2.64    | 16 | 3.00            | 2 | 1.105   | .368    |
| Availability & supply of materials & labour | 2.72 | 19 | 2.70      | 10 | 2.82              | 20 | 3.00       | 17 | 2.36    | 23 | 3.00            | 2 | .856    | .499    |
| Over Estimation                             | 2.72 | 19 | 2.60      | 16 | 2.82              | 20 | 3.00       | 17 | 2.45    | 18 | 3.00            | 2 | .670    | .617    |
| Insurance cost                              | 2.72 | 19 | 2.50      | 22 | 2.91              | 17 | 3.00       | 17 | 2.45    | 18 | 3.00            | 2 | 1.186   | .332    |

| Extent of Risk               | All  |    | Architect |    | Quantity Surveyor |    | Contractor |    | Builder |    | Project Manager |   | f value | p value |
|------------------------------|------|----|-----------|----|-------------------|----|------------|----|---------|----|-----------------|---|---------|---------|
|                              | Mean | R  | Mean      | R  | Mean              | R  | Mean       | R  | Mean    | R  | Mean            | R |         |         |
| Late arrival of materials    | 2.72 | 19 | 2.50      | 22 | 2.82              | 20 | 3.13       | 12 | 2.45    | 18 | 3.00            | 2 | 1.166   | .341    |
| Bad weather                  | 2.70 | 23 | 2.40      | 26 | 2.91              | 17 | 3.00       | 17 | 2.45    | 18 | 3.00            | 2 | 1.308   | .285    |
| Contractors' poor management | 2.67 | 24 | 2.60      | 16 | 2.82              | 20 | 3.00       | 17 | 2.27    | 27 | 3.00            | 2 | 1.265   | .301    |
| Expertise of construction    | 2.67 | 24 | 2.60      | 16 | 2.82              | 20 | 2.88       | 27 | 2.36    | 23 | 3.00            | 2 | .804    | .530    |
| Mode of financing            | 2.67 | 24 | 2.50      | 22 | 2.82              | 20 | 3.00       | 17 | 2.36    | 23 | 3.00            | 2 | 1.156   | .345    |
| Method of construction       | 2.65 | 27 | 2.60      | 16 | 2.73              | 28 | 2.88       | 27 | 2.36    | 23 | 3.00            | 2 | .838    | .509    |
| Variations (Technical)       | 2.63 | 28 | 2.40      | 26 | 2.82              | 20 | 3.00       | 17 | 2.27    | 27 | 3.00            | 2 | 1.799   | .149    |
| Changes in Clients taste     | 2.56 | 29 | 2.40      | 26 | 2.64              | 29 | 2.88       | 27 | 2.27    | 27 | 3.00            | 2 | 1.373   | .261    |

Source: Data Analysis Result 2022

## 5 Conclusion and Further Research

The current study examined the risk factors causing variability between CS and FAS and appraised the magnitude of agreement from stakeholders' perspectives. Findings revealed fifteen significant risk factors causing variability between CS and FAS within. From the data collected, the mean score analysis, degree of risk analysis and analysis of variance(ANOVA) revealed the top five risk variables in traditionally procured construction projects that impact variability between CS and FAS: Poor programme scheduling, other risks, Availability of design information, Fluctuation and Type of client, which was in concordance with some previous authors like (Odeyinka et al., 2012), (Offei-Nyako et al., 2016) and (Adafin et al. 2016, 2017 and 2020),but for other risk that includes insecurity, social vices and corruption/abuse of office and power.

Furthermore, the study observed a high concordance of participants with the factors identified. As a significant contribution, this study expands researchers' views of the construction community universally regarding the relationship between various risk variables and the attending result on costs in the construction industry in Nigeria and other countries where this issue is under-researched, and framework to be developed as the research is still on going. The knowledge also provides proper risk analysis (guidelines) that could assist construction stakeholders in measuring cost risks and managing risk practically.

## 6 Acknowledgements

The authors wish to acknowledge the contributions of Tertiary Education Trust Fund of Nigeria (TETFund) for funding the PhD.

## 7 References

Adafin, J, Rotimi, J O B and Wilkinson, S (2015) Why do the design-stage elemental cost plan and final tender sum differ in New Zealand. *Journal of Financial Management of Property and Construction*, 20(2), 116-131.

- Adafin, J, Rotimi, J O B and Wilkinson, S (2016) Risk impact assessments in project budget development: Architects' perspectives, *Architectural Engineering and Design Management*, 12(3), 189-204.
- Adafin, J, K (2017) *Prediction of Final Tender Sums of Construction Projects from the Design-Stage Elemental Cost Plans: A Decision Support Tool for New Zealand*. PhD Thesis, The University of Auckland, Auckland, New Zealand.
- Adafin, J, Rotimi, J O B and Wilkinson, S (2018) Risk impact assessments in project budget development: Quantity surveyors' perspectives, *International Journal of Construction Management*, 12(3), 1-16.
- Adafin, J, Rotimi, J O B and Wilkinson, S (2020) "An evaluation of risk factors impacting Project budget performance in New Zealand", *Journal of Engineering, Design and Technology*, 19, 41–61.
- Agyekum-Mensah, G (2018) The degree of accuracy and factors that influence the uncertainty of SME cost estimates, *International Journal of Construction Management*, Allahaim, F. S., & Liu, L. (2015). Causes of cost overruns on infrastructure projects in Saudi Arabia. *International Journal of Collaborative Enterprise*, 5(1-2), 32-57.
- Ameyaw, E E, Chan, A P C, Owusu-Manu, D G and Coleman, E (2015) A fuzzy model for evaluating risk impacts on variability between contract sum and final account in government-funded construction projects, *Journal of Facilities Management*, 13(1), 45-69.
- Arif, F, Lodi, S H and Azhar, N (2015) Factors influencing accuracy of construction project cost estimates in Pakistan: perception and reality, *International Journal Construction Management*, 15(1), 59-70.
- Ashworth, A., and Hogg, K. (2007). *Willis's Practice and Procedure for the Quantity Surveyor*, 12<sup>th</sup> Edition, Blackwell Science, Oxford London.
- Carter, B, Hancock, T, Morin, J and Robins, N (1994) *Introducing Riskman Methodology: the European Project Risk Management Methodology*. Oxford: Blackwell Publishing.
- Doloi, H K. (2011) "Understanding stakeholders' perspective of cost estimation in project Management." *International Journal of Project Management*, 29(5), 622-636.
- Dosumu, B., Ejohwomu, O., & Yunusa-Kaltungo, A. (2021, June). A Systematic Review on Development of a Project Cost Estimation Framework: a Case Study of Nigeria. In *Proceedings of the Construction Business and Project Management Conference Cape Town, South Africa, 24–25 June 2021*. (p. 137).
- El-Sayegh, S.M. and Mansour, M.H., (2015). Risk Assessment and Allocation in Highway Construction Projects in the UAE. *Journal of Management in Engineering*, 31(6), 1-11
- Enshassi, A Mohamed, S and Abdel-Hadi, M (2013) Factors affecting the accuracy of pretender cost estimates in the Gaza strip, *Construction in Developing Countries*, 18(1), 73-94.
- Fellows, R and Liu, A (2008) *Research Methods for Construction*. Oxford: Blackwell Publishing Ltd.
- Hwang, B G, Zhao, X and Toh, L P (2014) Risk management in small construction projects in Singapore: status, barriers and impact, *International Journal of Project Management*, 32, 116-124.
- Khan, S.H., Z. Azhar, S. Parveen, F. Naeem and M.M. Sohail, (2011). Exploring the Impact of Infrastructure, Pay Incentives and Workplace Environment on Employees

- Performance (A case study of Sargodha University). *Asian Journal of empirical research*, 2(4), 118-140.
- Love, P E D and Ahiaga-Dagbui, D D (2018) Debunking fake news in a post-truth era: the plausible untruths of cost underestimation in transport infrastructure projects, *Transport Research Part a*, 113(2018), 357-368.
- Naoum, S G (2007) *Dissertation Research and Writing for Construction Students*. UK: Elsevier Ltd.
- National Bureau of Statistics (NBS). (2021). Consumer price index: August 2021. NBS Nigeria. Retrieved from [www.nigerian-stat.gov.ng](http://www.nigerian-stat.gov.ng). Assessed 18/10/2021.
- Odeyinka, H, Larkin, K, Weatherup, R, Cunningham, G, McKane, M and Bogle, G (2012). *Modelling Risk Impacts on the Variability Between Contract Sum and Final Account*. UK: Royal Institution of Chartered Surveyors, 1- 19.
- Offei-Nyako, K., Tham, L. C. O., Bediako, M., & Abodor, C. D. (2016). Deviations between Contracts sums and final accounts: the case of capital projects in Ghana.
- Salahi P and Ali E O (2018) Integrated Risk of Progress-Based Costs and Schedule Delays in Construction Projects *Engineering Management Journal*, 30:2, 108-116, DOI: 10.1080/10429247.2018.1439636
- Simpeh, E. K., Ndiokubwayo, R., Love, P. E., & Thwala, W. D. (2015). A rework Probability model: a quantitative assessment of rework occurrence in construction Projects. *International Journal of Construction Management*, 15(2), 109-116.
- Wibowo, M.A. (2004). *The Contribution of the Construction Industry to the Economy of Indonesia: A systemic Approach*.
- Yap, J B H, Abdul-Rahman, H, Wang, C and Skitmore, M (2018) Exploring the underlying factors inducing design changes during building production, *Production Planning and Control*, 29(7), 586-601.
- Zakaria, Z., Ismail, S. and Yusof, A. (2013) Cause and Impact of Dispute and Delay the Closing of Final Account in Malaysia Construction Industry, *Journal of Southeast Asian Research*, (June), pp 1–12. DOI:10.5171/2012.975385